

REQUEST FOR QUOTES – RFQ 09-26-25WW

Wave Wall Phase 3 Upgrades

Issue Date: Friday, September 26, 2025

Mandatory Site Visit: Wednesday, October 1, 2025 11:00 AM

Submission Deadline: Wednesday, October 8, 2025 3:30 PM



1. PROJECT LEAD – CONTACT INFORMATION

Town of Placentia

Rodney Cooney, Public Works Foreman

Cell: 709-227-1534

2. PROJECT LOCATION

Adjacent to properties located at 118-120 Orcan Drive, Placentia (from the intersection at Swan's Road to the intersection at O'Keefe's Road intersection).


3. BACKGROUND

The sheet steel wave wall along Orcan Drive has intermittent holes, damaged pipe and is generally deteriorating at different points along the approximate one-mile structure. It is not feasible for the Town to replace the entire structure; therefore, we have undertaken the process of patching the wall in increments. The process of patching wall sections from 102 – 116 Orcan Drive was completed in 2024 and in the spring of 2025. The Town of Placentia is now moving forward with Phase 3 of the repair process.

4. **PROJECT DELIVERABLES** The Town intends to continue mitigation efforts in a third segment of the wall at this time. There will be an approximate 43m segment of wall at #118-120 Orcan Drive to be completed this fall.

It is the Town's intention to retain the services of a local contractor to:

- encase thirteen (13) pieces of existing 600 mm pipe with 2.4m steel wall /100mm concrete cover;
- remove sidewalk, excavate, construct forms, pour concrete and backfill to seal a steel wall with a minimum depth of 100mm of concrete;

- 
- concrete sidewalk can be removed and reinstalled; however damaged sections of the sidewalk that cannot be reused must be replaced at the contractor's expense;
 - topsoil and sods are to be replaced (hydroseed acceptable); site cleanup required.
 - wall section is to be patched below the steel channel tie back system to a depth of 1.2m;
 - contractor is to patch holes in sheet piling prior to pouring 25 MPa concrete;
 - excavated materials may contain wood cribbing that cannot be used for backfilling excavation; otherwise, on-site materials can be reused for this purpose. Contractor is to supply additional backfill material as required.
 - contractor is responsible for disposal of wood cribbing.
 - full cleanup and proper disposal of debris is required with the site being restored to an acceptable condition.

Contractors are advised that they are required to patch the wall in sections due to the condition of the existing wall. Contractor is to determine the length of the wall section to be poured. A site visit will be scheduled to provide contractors with specifics of the existing infrastructure and provide an opportunity for questions and answers to clarify any details.

5. TIMELINES

A. MANDATORY SITE VISIT

All prospective bidders are required to attend a **Wednesday, October 1, 2025 at 11:00 A.M** with the Town of Placentia's Public Works Foreman. The site visit is mandatory to ensure that all prospective bidders are fully aware of the location and condition of existing infrastructure and to obtain a clear perspective of what is required as an end result of this project.

B. DATE OF ISSUE

This Request for Quotations is being **issued Friday, September 26, 2025** notice of which is distributed to local contractors and posted on Town of Placentia media sites – Facebook and website www.placentia.ca.



C. DEADLINE FOR SUBMISSION

Contractors are requested to **submit quotes on or before 3:30 PM Wednesday, October 8, 2025.**

D. PROJECT COMPLETION DATE

The successful bidder is required to meet the project **completion date of November 21, 2025.**

6. BID PROCESS

- A. Bidders must submit quotes on the bid form provided in **Appendix A.**
- B. All bidders are required to submit a **bid security of \$5,000.00** in the form of a bank draft, bid bond or certified cheque together with their bid document.
- C. The successful candidate's bid security will be retained by the Town of Placentia until the project is successfully completed to the satisfaction of the Town of Placentia.
- D. All other bid securities received will be returned to the unsuccessful bidders following the execution of the agreement between the Town of Placentia and the successful bidder.
- E. Submissions are to **hand delivered to the Town Hall** office on **25 Patterson Drive** – the envelope should be clearly marked to:

**Attention of the CAO
Wave Wall Phase 2 Upgrades
25 Patterson Drive**

Contract Award

The bids received will be duly recorded. The successful bidder will be notified in writing (via email) and a Purchase Order will be issued upon acceptance of the work.

The Town of Placentia reserves the right to select the bidder based on submissions; the lowest or any quote is not necessarily accepted.



APPENDIX A
Wave Wall Upgrades Phase 3
BID FORM

1. Instructions on How to Complete Bid Form

Rates quoted by the bidder must be all-inclusive (labour, equipment and material costs, all mobilization and demobilization costs, insurance costs, and all other overhead) with HST being a separate line item.

Prices are to be listed as follows:

3. Bid Form

QUOTE TO:

1. Encase 13 existing pipes
(2.4m steel wall/100mm concrete cover)
13 each @ \$ _____ per \$ _____

2. Remove existing sidewalk, construct forms and pour 100 mm
concrete wall, remove forms and replace concrete sidewalk
and sods (hydroseed acceptable) to pre-start condition as
detailed in Section 4: Project Deliverables
43m @ \$ _____ per metre \$ _____

- Subtotal** \$ _____
- HST** \$ _____
- Total** \$ _____

Name & Address & Phone # of Company

Name & Signature of Company Signatory
