

**RFQ – REPLACEMENT OF DILAPIDATED FENCE  
BROOK LANE, FRESHWATER  
DECEMBER 1, 2025**

The Town of Placentia intends to replace dilapidated fencing on Brook Lane, Freshwater and is seeking the services from a local contractor to complete the work, particulars of which are outlined below. **Interested contractors may attend a site visit with Public Works Superintendent, Rodney Cooney on Tuesday, December 2, 2025 @ 10:00 AM.**

This is a limited call for quotes to:

- Remove existing fencing and dispose of damaged material as per provincial guidelines.
- Stabilize groundwork following removal to ensure the integrity for new fence installation.
- Supply and install a Type 1, Class A medium style fence
  - ✓ 9 gauge chain link fencing
  - ✓ 135 m long
  - ✓ 1.2 m high
  - ✓ New fence posts to be installed in concrete extending 50 mm above ground level
    - Posts at beginning of fence and then placed 3 m apart with final post at the end of the fence
    - Posts to be at a depth of 1200 mm X 300mm diameter and extend 50mm above ground level – sloped to drain and secured in concrete.
    - Complete with end caps
- Contractors are to reuse undamaged existing posts, top rail and fittings where feasible.
- Contractors will supply new posts where required; corner posts are to be 4” in diameter; remaining post size is to be per industry standard.
- Contractors will supply and install all new posts, top rail, fittings and mesh as required.
- All materials are to be galvanized.

Quotes: Are to be submitted by email addressed to [townofplacentia@placentia.ca](mailto:townofplacentia@placentia.ca) on or before close of business on Monday, December 8, 2025.

Questions: Further information regarding this RFQ may be directed in writing to Rodney Cooney; email [director@placentia.ca](mailto:director@placentia.ca).

*We thank you for your interest in Town of Placentia projects – bids received will be posted to the Town of Placentia website – [www.placentia.ca](http://www.placentia.ca)*